SENSOR SCHEDULE

	DESCRIPTION	MANUFACTURER	MODEL	MOUNTING	NOTES	COUNT
SENSORS/ SWITCHES						
OS a	MULTI TECHNOLOGY WALL OCCUPANCY SENSOR	WATTSTOPPER	DT-200	WALL		28
SENSORS/ SWITCHES						
RCL1	0-10V DIMMING ROOM CONTROLLER - 2 ZONE	WATTSTOPPER	LMRC-111 OR APPROVED EQUAL	ABOVE CEILING		16
RCL2	0-10V DIMMING ROOM CONTROLLER - 2 ZONE	WATTSTOPPER	LMRC-112 OR APPROVED EQUAL	ABOVE CEILING		1
RCL3	0-10V DIMMING ROOM CONTROLLER - 3 ZONE	WATTSTOPPER	LMRC-213 OR APPROVED EQUAL	ABOVE CEILING		5
S LV1	LOW VOLTAGE 1-BUTTON OVERRIDE WALL SWITCH	WATTSTOPPER	LMSW-101-W OR APPROVED EQUAL	WALL	INCLUDE CAT5E JUMPER WITH RJ45 CONNECTORS TO ROOM CONTROLLER	31
S LV2	LOW VOLTAGE 2-BUTTON OVERRIDE WALL SWITCH	WATTSTOPPER	LMSW-102-W OR APPROVED EQUAL	WALL	INCLUDE CAT5E JUMPER WITH RJ45 CONNECTORS TO ROOM CONTROLLER	43
OS1	LOW VOLTAGE CEILING OCCUPANCY SENSOR	WATTSTOPPER	LMDC-100 OR APPROVED EQUAL	CEILING	INCLUDE CAT5E JUMPER WITH RJ45 CONNECTORS	24
S LVD1	LOW VOLTAGE DIGITAL DIMMER WALL SWITCH	WATTSTOPPER	LMDW-101-W OR APPROVED EQUAL	WALL	INCLUDE CAT5E JUMPER WITH RJ45 CONNECTORS TO ROOM CONTROLLER	16
DLS	LOW VOLTAGE DIMMING DIGITAL DAYLIGHT SENSOR.	WATTSTOPPER	LMLS OR APPROVED EQUAL	CEILING	INCLUDE CAT 5E JUMPER WITH RJ45 CONNECTORS TO ROOM CONTROLLER	1
S LV	LOW VOLTAGE MOMENTARY CONTACT SWITCH	WATTSTOPPER	DCC2	WALL		221
S TS	LOW VOLTAGE TIMER SWITCH	WATTSTOPPER	TS-400-24	WALL		186
OS a	MULTI TECHNOLOGY CEILING OCCUPANCY SENSOR	WATTSTOPPER	DT-300	CEILING		1244
S O	MULTI TECHNOLOGY WALL MTD OCCUPANCY SENSOR	WATTSTOPPER	DSW-100(LINE) DSW-100-24(LV)	WALL		28
PLC	ON/OFF LOAD CONTROLLER	WATTSTOPPER	WATTSTOPPER LMPL-101 OR APPROVED EQUAL	ABOVE CEILING	INCLUDE CAT-5E JUMPER BETWEEN PLC AND RLC	1
SENSORS/SWITCHES						
ER1	EMERGENCY LIGHTING CONTROL UNIT	WATTSTOPPER	ELCU-200 OR APPROVED EQUAL	ABOVE CEILING		1

GENERAL NOTES:
A. REFER TO ELECTRICAL SPECIFICATIONS FOR ADDITONAL REQUIREMENTS WHICH MAY NOT NECESSARILY BE REFLECTED IN CATALOG NUMBER AND/OR DESCRIPTION IN THIS SCHEDULE.

NOTES:
1. CONTRACTOR TO PROVIDE THE APPROPRIATE NUMBER OF POWER PACKS FOR PROJECT. COORDINATE WITH THE MANUFACTURER FOR THE CORRECT QUANTITY.
2. CONTRACTOR TO PROVIDE 4X4 JUNCTION BOXES.
3. PROGRAM WALL-MOUNTED OCCUPANCY SWITCH INDICATED AS A VACANCY SENSOR AND 5-MINUTE TIMER.
4. TIMER-SWITCH INDICATED FOR CONTROL OF HOT AISLE FIXTURES SHALL BE SET TO 15-MINUTES.
5. OCCUPANCY SENSORS IN PLENUM SPACE SHALL BE PROVIDED WITH PLENUM RATED POWER PACK AND PLENUM RATED LOW VOLTAGE WIRING TO LUMINAIRE.
6. ELECTRICAL CONTRACTOR SHALL SUBMIT COMPLETE LIGHTING CONTROL MANUFACTURER'S SHOP DRAWING AND PRODUCT SUBMITTAL FOR APPROVAL.

LIGHTING CONTROL MATRIX

ROOM TYPE	MANUAL CONTROL			AUTOMATIC ON/OFF CONTROL								OTHER				COMMENTS
						SETTINGS										
	SWITCH	TIMER SWITCH	DIMMER OF SCENE CONTROL	TIMECLOCK	OCCUPANCY SENSOR	FULL ON	PARTIAL ON	MANUAL ON	FULL OFF	PARTIAL OFF	DAYLIGHT RESPONSIVE CONTROL	RECEPTACLE CONTROL (50% RECEPTACLES)	RECEPTACLE CONTROLS (25% FURNITURE BRANCH CIRCUITS)	DEMAND RESPONSE	
INTERIOR															
CONFERENCE, BREAK ROOM			•		•			•	•			•			
CORRIDOR			•		•	•				•					
LOBBY	•			•	•	•			•	•					
LOADING DOCK	•			•			•		•						
OPEN OFFICE (>250 SQ. FT)			•		•		•		•				•		
PRIVATE OFFICE (<250 SQ. FT)			•		•			•	•			•			
RESTROOM					•	•				•					
PRIVATE RESTROOM	•				•	•			•						
STAIRWELL						•									
STORAGE ROOM	•				•			•	•						
TELECOM / ELECTRICAL / MECHANICAL ROOMS	•				•	•			•						
DATA HALL															
MAIN AISLE - ZONED PER PLANS	•				•		•			•					
HOT AISLE		•													
COLD AISLE	•				•		•		•						

ROOM TYPE	MANUAL CONTROL			AUTOMATIC ON/OFF CONTROL								OTHER				COMMENTS
						SETTINGS										
	SWITCH	TIMER SWITCH	PHOTOCELL	TIMECLOCK	MOTION SENSOR	FULL ON	PARTIAL ON	MANUAL ON	FULL OFF	PARTIAL OFF						
EXTERIOR																
FACADE / LANDSCAPE			•	•												
PARKING LOT LIGHTING			•	•	•	•				•						LIGHTING TO BE REDUCED TO 50% WHEN NO ACTIVITY IS DETECTED FOR 15 MINUTES.
DRIVE AISLE LIGHTING			•	•												
SECURITY ENTRANCE LIGHTING			•	•												
ROOF LIGHTING	•		•		•	•			•							
GENERATOR PLATFORM LIGHTING	•		•		•	•			•							
GENERATOR YARD LIGHTING			•		•	•			•							
OTHER EXTERIOR			•	•												

LCP-1 LIGHTING CONTROL RELAY SCHEDULE

RELAY #	CONTROL AREA	PANEL	CKT	FIXTURE TYPE	DEVICE GROUP ID
1	SOUTH DRIVE	SLP-1	3	HP/HP1	a
2	WEST DRIVE	SLP-1	1	HP	b
3	EAST DRIVE	SLP-1	2	HP	c
4	ENTRY CANOPY	SLP-1	27	D1	d
5	GEN YARD	SLP-1	6	HE/H1A	e
6	EGRESS DOORS	SLP-1	4	HE	f
7	BLDG. MOUNTED FIXTURES	SLP-1	7	H	g
8	BLDG. MOUNTED FIXTURES	SLP-1	5	H	h
9	BLDG. MOUNTED FIXTURES	SLP-1	11	H	i
10	GEN PLATFORM	SLP-1	8	G11E	j
11	GEN PLATFORM	SLP-1	18	G11E	k
12	GEN PLATFORM	SLP-1	23	G11E	l
13	GEN PLATFORM	SLP-1	19	G11E	m
14	GEN PLATFORM	SLP-1	20	G11E	n
15	GEN PLATFORM	SLP-1	21	G11E	o
16	ROOF	SLP-1	10	R	p
17	LOW ROOF	SLP-1	25	HW3	q

2 LCP-1 LIGHTING CONTROL RELAY SCHEDULE
E-92001 | NTS

LCP-2 LIGHTING CONTROL RELAY SCHEDULE

RELAY #	CONTROL AREA	PANEL	CKT	FIXTURE TYPE	DEVICE GROUP ID
1	SECONDARY ENTRANCE	SLP-2	1	HP	a
2	MAIN DRIVE	SLP-2	10	HP	b

3 LCP-2 LIGHTING CONTROL RELAY SCHEDULE
E-92001 | NTS

LCP-3 LIGHTING CONTROL RELAY SCHEDULE

RELAY #	CONTROL AREA	PANEL	CKT	FIXTURE TYPE	DEVICE GROUP ID
1	MAIN DRIVE	SLP-3	2	HP	a
2	GUARDBOOTH	SLP-3	22	HP2	b
3	MAIN ENTRANCE	SLP-3	24	HP	c

4 LCP-3 LIGHTING CONTROL RELAY SCHEDULE
E-92001 | NTS

AHJ STAMP

CONFIDENTIAL

PROJECT ADDRESS
2341 ECHO ROAD
LITHIA SPRINGS, GEORGIA 30122

PROJECT DELIVERY PACKAGE
PERMIT

SEAL/SIGNATURE

THE LICENSED PROFESSIONAL SEAL AFFIXED TO THIS SHEET APPLIES ONLY TO THE MATERIAL AND ITEMS SHOWN ON THIS SHEET. ALL DRAWINGS, INSTRUMENTS OR OTHER DOCUMENTS NOT EXHIBITING THIS SEAL SHALL NOT BE CONSIDERED PREPARED BY THIS PROFESSIONAL, AND THIS PROFESSIONAL EXPRESSLY DISCLAIMS ANY AND ALL RESPONSIBILITY FOR SUCH PLAN, DRAWINGS OR DOCUMENTS NOT EXHIBITING THIS SEAL.

LEGAL NOTICE
THIS INFORMATION IS VOLUNTARILY SUBMITTED TO A PUBLIC OFFICE IN EXPECTATION OF PROTECTION FROM DISCLOSURE AS PROVIDED BY SECTION 149.433 OF THE REVISED CODE

ISSUE DATE: 15JUL2025 | PROJECT NO: ATL088

REV.	DATE	DESCRIPTION	DRWN/CHK
0	15JUL2025	PERMIT	SRI

CONFIDENTIAL
ANY UNAUTHORIZED USE OR REPRODUCTION OF THIS DOCUMENT IN WHOLE OR IN PART IS PROHIBITED. DELETE THIS DOCUMENT IF YOU HAVE RECEIVED IT IN ERROR.

MECHANICAL ENGINEER:
SWANSON RINK
MICAH GUILD, PE
303.832.2666
1120 LINCOLN STREET, STE 1200
DENVER, CO 80203

ELECTRICAL ENGINEER:
SWANSON RINK
ALI GHAMKHAR, PE
303.832.2666
1120 LINCOLN STREET, STE 1200
DENVER, CO 80203

CIVIL ENGINEER:
BOHLER
BRETT BUCKLAND
678.695.6800
211 PERIMETER CNTR PKWY, STE 425
ATLANTA, GA 30346

STRUCTURAL ENGINEER:
S. A. MIRO
DARYL T. BARONE
303.741.3737
4582 S. ULSTER STREET, SUITE 750
DENVER, CO 80237

ARCHITECT:
GENSLER
KEVIN BONGER
404.507.1000
999 PEACHTREE STREET NE, STE 100
ATLANTA, GA 30309

FIRE PROTECTION ENGINEER:
SWANSON RINK
MICAH GUILD, PE
303.832.2666
1120 LINCOLN STREET, STE 1200
DENVER, CO 80203

TELECOM ENGINEER:
SWANSON RINK
ALI GHAMKHAR, PE
303.832.2666
1120 LINCOLN STREET, STE 1200
DENVER, CO 80203

SECURITY ENGINEER:
EXANTE360
MIKE RIDGLEY
214.840.7305
895 DOVE ST #3, NEWPORT BEACH CA 92660

PROJECT: BUILDING A

TITLE: LIGHTING SCHEDULES

SHEET NO: E-92001

FILE NO: ATL088-SRI-10-XX-DR-E-92001

PAPER SIZE: ARCH E1 | SCALE: 12" = 1'-0" | REV: 0

PDF PRINT DATE: 7/14/2025 11:08:19 AM BASED ON TEMPLATE VERSION: BOD 24IH OPTIDC 2.4